

BOQ for " Plantation work alongside road Berm from "D" gate to Banduhurang waste yard & magazine side."					
			NIT NO BND/CIV-63		
Sl.No	Description	Quantity	Unit	Rate	Amount
				Rs. P	Rs. P
1	Supply and stacking of good earth at site including royalty and carriage up to 3 km (earth measured in stacks will be reduced by 20% for payment)	50	cum		
	(Rate in Words)				
2	Supplying and stacking manure at site including royalty and carri-age up to 13km (Siudge measured in stacks will be reduced by 8% for paymen.	15	cum		
	(Rate in Words)				
3	Mixing earth and sludge or manure in proportion specified or directed.	65	cum		
	(Rate in Words)				
4	Digging holes in ordinary soil and refilling the same with the exca-vated earth mixed with manure or sludge in the ratio of 2:1 by volume(2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%)flooding with water, dressing including remove of rubbish and surplus earth, if any with all leads and lifts (Cost of manure,siudge or extra good earth if needed to be paid for separately): Holes 60 cm dia,and 60cm deep.	2000	each		
	(Rate in Words)				
5	Making tree guard with bamboo 1m x 1m x 1.5m as per standard design.	100	each		
	(Rate in Words)				
6	Filling mixture of earth and sludge or manure in the desired proportion in trenches, flooding with water and leveling (cost of supplying earth and sludge or manure and mixing excluded).	65	cum		
	(Rate in Words)				

7	Plantation of Avenue plant & ornamental plant like Ashok long folia / Ashok pendula / Palianthis longo folia / Crotons / Rose / Musanda / Bhasindi / Rexona / Jahou / Palm / singapuri Exora plants etc, including supplying of plants not less than 16" long and watering during the plantation and complete maintenance of 100 days this will be reckoned from the date of completion above work i.e. after 03 months.	2000	each		
	(Rate in Words)				