

URANIUM CORPORATION OF INDIA LIMITED
P.O.- JADUGUDA MINES, EAST SINGHBHUM, JHARKHAND

Ref. No. - UCIL/Civil-Mill/2025/DOP-28/01

Dated-06.11.2025

ENQUIRY

Sealed quotation are invited from individual/firm for **"Flooring and Brickwork for Hazardous Waste/Used Oil Storage Shed at Scrap Yard of Jaduguda Mill (Under DOP-28)"**


To,

1. M/s P. S. Construction.
2. M/s A. K. Enterprises.
3. M/s. R. K. Enterprises.

Terms & Conditions:

1. The quotation to be addressed to the **"Additional Superintendent (Civil) Mill Jaduguda, P.O.-Jaduguda Mines, East Singhbhum, Jharkhand-832102"** as per attached format with acceptance of terms & conditions mentioned in the format.
2. UCIL has the right to accept or reject any or all the application without any assigning a reason thereof.
3. The time and date of submission of quotation is **"03:00 PM on or before 08.11.2025"**. The quotation shall be opened on **08.11.2025** the same day at **03:30 PM.**

Yours Truly
For Uranium Corporation of India Limited


06.11.2025
Addl. Supdt. (Civil) Mill Jaduguda


सुलभ कुमार बैस
Sulabh Kumar Bais
अपर अधीक्षक (सिविल) मिल / जादुगोड़ा
Addl Supdt. (Civil) Mill / Jaduguda

Copy forwarded to:

1. Supdt.(CP)- Kindly upload in UCIL web page.
2. Office File.


SCHEDULE OF ITEM AND RATE

<u>"Flooring and Brickwork for Hazardous Waste/Used Oil Storage Shed at Scrap Yard of Jaduguda Mill (Under DOP-28)"</u>					
Ref. No. - UCIL/Civil-Mill/2025/DOP-28/01, Dated-06.11.2025					
Sr. No.	Item	Quantity	Unit	Unit rate i/c GST (In Rs.)	Total amount i/c GST (In Rs.)
1	Laying plain cement concrete 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size) for floors, drain, pavement, hard surfacing including loading, unloading, transportation of materials from stock yard to work site. Finishing concrete surface, in line, level, curing, de-watering etc. all complete as per specification and instruction of the EIC.	13.00	Cum		
2	Reinforced cement concrete work in foundation and superstructure and walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size) (. All complete as per specification and drawing or as directed by Engineer-in-charge.	20.00	Cum		
3	Providing and fixing straight shuttering for concrete works to anywhere at any level (Including staging) including strutting, providing etc. for all type of works. And removing of form or striking out after completion of works as directed and specified by the Engineer-in-charge.	10.00	Sqm		
4	Supply and fixing TMT bars of 500D and above for reinforced cement concrete work / brick work including transporting, decoiling, straightening, cutting, derusting, bending, placing in position at all height and binding with binding wire etc. complete as per drawing , specification and instruction of the Engineer-in-charge.	1830.00	Kgs		
5	1 st class brick work with bricks in superstructure at all heights in cement mortar 1:6 (1cement : 6 sand) to correct, line, level, and plumb including raking out the joints, curing, scaffolding, loading, unloading, transporting materials from stock yard to work site. Etc. all complete as per specification, drawing and directed by Engineer-in-charge.	10.00	Cum		


06.11.2025

सुलभ कुमार बैस
Sulabh Kumar Bais
अपर अधीक्षक (सिविल) मिल / जादुगोड़ा
Addl Supdt. (Civil) Mill / Jaduguda

6	15 mm thick cement plaster to all brick / concrete works etc. in walls of surfaces in cement mortar 1:6 (1 cement : 6 sand) including scaffolding , backing the surface , smoothen finishing to correct line level, plumb as required, curing loading, unloading, transportation of materials from stock yard to work site etc. complete at all levels etc. complete as per drawing , specification and instruction of the Engineer-in-charge.	39.00	SQM		
	Grand Total i/c GST (in Rs.)				
	Grand Total In Words -				


 06.11.2025
 सुलभ कुमार बैस
 Sulabh Kumar Bais
 अपर अधीक्षक (सिविल) मिल / जादुगोड़ा
 Addl Supdt. (Civil) Mill / Jaduguda

Other terms and conditions - Ref. No. - UCIL/Civil-Mill/2025/DOP-28/01, Dated-06.11.2025

1. Security Money Deposit:

Security money deposit equivalent to 10 (Ten) % of the ordered value is required to be deposited in accounts Department-UCIL in the form of demand draft before the start of the work. 100% SD will be refunded on written request in duplicate to the EIC after expiry of defect liability period.

2. Completion Time:

60 (Sixty) days (including Sunday & holiday) from the date of issue of work order.

3. Payment Terms:

One (1) R.A and One (1) Final Bill will be paid against this work after submission of quadruplicate bill. Final bill should be submitted within 30 (Thirty) days from the date of completion.

4. Working period:

General Shift (excluding Sunday, holiday) 07:00 AM to 12:00 Noon & 02:00 to 05:00 PM/as instructed by EIC.

5. Rate:

The rate shall be quoted by the contractor must include all taxes (GST) & Duties, PF, PPE, Insurance, etc. No extra payment will be entertained after rate quoted by the contractor.


6. All Statutory compliances like Minimum wages, EL, EPF, Bonus, Insurance, Safety appliances and tools & tackles, contractor's profit should be included in quoted rate. No extra payment will be made thereafter.

7. Contractor to execute contract agreement as per UCIL Account department on a stamp paper.

8. If any discrepancy found in figure & words of rate or amount of the price bid then rate or amount in words will be treated as final. Defect liability period – 01 Months. Contractor has to take ESIC/insurance for minimum 4 Nos of Workmen.

9. The Contractor shall at all times, take all reasonable precaution for the safety of employees, including those of sub-contractors in the performance of his contract and shall comply with all applicable provisions of both Central as well as the State Safety Laws. In addition to the Safety provision already included in the tender, the contractor will be sole responsible to ensure safety at work place and also to provide all PPE's to be provided by contractor to worker, no responsibility to UCIL. Contractor shall have at least one person fully trained in first Aid present at the site of work all the time.

10. Liquidated Damages (LD) shall be levied where reasons are attributable to contractor for delay in execution of contract. LD shall be levied @0.5% per week or part thereof on the value of unfinished supply/work order for each week of delay subject to a maximum of 5% of the total value of contract (excluding Taxes and Duties).


06.11.2025
Sulabh Kumar Bais
Addl. Supdt.(Civil) Mill Jad

सुलभ कुमार बैस
Sulabh Kumar Bais
अपर अधीक्षक (सिविल) मिल / जादुगोड़ा
Addl. Supdt. (Civil) Mill / Jaduguda